The design and construction challenges of utility scale PV plants

Abri Stegmann - July 2019





Introduction



My background:

- Stellenbosch studies
- Scatec Solar
 - An Independent Power Producer who develops, designs, builds, owns and operates utility scale PV plants all around the world.
 - ~1 GW of PV in operation
 - Projects in South Africa, Rwanda, Egypt, Brazil, Honduras, Malaysia, Ukraine, Argentina, Mozambique, Jordan, soon Vietnam.
 - Targeting 3.5 GW by 2021

Today I'll speak about:

- The typical challenges that we face in the utility scale solar industry.
 - Design challenges
 - Construction challenges
 - Examples
 - 25 min presentation and 5 min for Q&A


Copyright: Scatec Solar ASA www.scatecsolar.com · post@scatecsolar.com

Introduction

Snapshot of a Utility Scale PV Plant

REIPPP R4 Upington sites:

- 3 x 86 MWdc plants located in close proximity •
- ~700 000 PV modules ۲
- 1 020 000 km of DC cable •
- 180 x 1.45 MW inverters •
- 60 x 4.7 MW transformers •
- 720 x single-axis tracker drive systems •
- 130 000 tracker sub-structure posts •
- 24 weather stations •
- 30 000 SCADA signals ۲
- 600 Ha of land covered •





Introduction



Snapshot of a Utility Scale PV Plant



Copyright: Scatec Solar ASA www.scatecsolar.com • post@scatecsolar.com

Introduction



Snapshot of a Utility Scale PV Plant




Copyright: Scatec Solar ASA www.scatecsolar.com • post@scatecsolar.com





Constantly new technologies: PV Modules

Best Research-Cell Efficiencies



Copyright: Scatec Solar ASA www.scatecsolar.com • post@scatecsolar.com



Constantly new technologies: PV Modules

2013 – 240Wp modules 2019 – 410Wp modules

Ordering a module in 2013: Please give me a poly-Si 240Wp module

<u>Ordering a module in 2019</u>: Please give me a mono-Si, PERC, Bi-facial, Double glass, 1 500Vdc rated module with an anti-reflective coating, light reflective film, half cut cell, triple busbar, 1.2m long 4mm² string cable with MC4-compatable cable terminations. Don't even specify the watt-class...

Manufacturers have so many options that it is difficult to compare them to each other.

Manufacturer: What do you want? Me: What do you have? Manufacturer: What do you need? Me: I don't know what I need. What do you offer? Manufacturer: We offer whatever you require.



Constantly new technologies: Inverters

2013 – up to 10 kW String and 850 kW Central inverters 2019 – up to 250 kW String and 5 MW Central inverters

Central vs string inverters, battery storage, plant control, DC systems, etc.





Constantly new technologies: Misc.

Floating solar systems Bifacial systems Hybrid systems Etc.





Difficult locations and environments

We've either built or is in the process of designing plants in:


- Bangladesh: Swamp land Waterlogged areas
- Egypt: Desert Dry, remote, hot and dusty
- Brazil: Jungle High vegetation growth, environmentally sensitive
- Malaysia: Monsoon High rainfall >2.1 m/annum
- Ukraine: Snowfall and sub-zero temperatures
- Rwanda: Remote, weak grid, high lightning area
- South Africa's "Droë" Karoo



Copyright: Scatec Solar ASA www.scatecsolar.com • post@scatecsolar.com




Drainage





Drainage





Difficult locations and environments

Often very limited or bad quality information from site. To assess a potential project site, we have to know as a minimum:

- Geotechnical conditions (sub-soil condition, soil types, earth quakes, etc)
- Environmental conditions (rainfall, irradiation, wind speed, snow, dust, etc)
- Site topography (accurate topo needed to assess shading and sub-structure)
- Grid condition (spare capacity, extensions planned, grid impact study)
- Local legislation, contracts, standards, etc.
- Local expertise (companies, labour, etc)
- Specific local requirements (eg. airports, radio interference locations, etc.)

Customers

Utilities:

- Don't know how solar works
- Resistant to change and competition
- Inadequate or vague grid codes
- Unstable or unreliable grids
- Old infrastructure and poor maintenance

Mines:

- Don't know their own systems
- Don't know what they require

Private PPAs:

• Islanded systems or reliance on utilities








Lightning protection for large PV plants

Standards have not kept up with developments in PV. No single clear answer on how to adequately protect free field PV systems, only guidelines.



www.scatecsolar.com · post@scatecsolar.com





Logistics challenges:

- During peak construction about 60 interlink trucks deliver material to site very day for 2-3 months.
- Warehouse management system has to be in place (FIFO/FILO systems)
- Need the correct materials to arrive at the correct time and location (JIT system)
- Large quantities of people to manage (up to 1200 people on site)
- Fast training programs to equip unskilled labour people
- Communication on site (remote, no cellular network, no radios allowed)

Planning challenges:

- Large quantities of unskilled labour, sometimes constantly changing
- Short construction timelines
- Accurate reporting back from construction personnel
- Multiple contractors and equipment suppliers involved



Multiple processes running in parallel. Effectively tracking progress is important!





Quality challenges:

• How to keep a standard of quality across a large site, multiple teams, etc.

Examples:

- Incorrect survey increases bulk earth work quantities by 800 000m³
- Incorrect fastening of cables resulted in 1 000 000 cable tie replacements
- Incorrect torqueing of bolts results in 3000 modules' cracked glass





PV construction is handled similarly to a manufacturing operation:

First make a prototype, then automate production.

Small efficiently improvements mean large project time impacts.

Example:

- 1 minute to mount a PV module
- Mounting 700 000 modules would take ~12 weeks*

Shaving off 5 seconds off of the installation time:

- 55 seconds to mount a PV module
- Mounting 700 000 modules would take ~11 weeks*

Shaving 1 week off installation time. This could be the difference between using a cordless drill versus a spanner to fasten the module's holding bolts.



Unique construction tasks: Removing 4 000 palm oil trees.





Unique construction tasks: Fast growing vegetation





Unique construction tasks: Complex civil works (water, sand, organic material)



66 MWp plant in Malaysia



Unique construction tasks: Hard ground





Unique construction tasks: Irregular shapes





Commissioning and plant testing:

- Multiple parties on site during commissioning
- 1000V vs 1500Vdc system change Testing technology behind
- Some tests are weather dependent.
- Testing with a utility can be "painful" but is unavoidable
- Explaining to stakeholders how the plant operates and that it is healthy
- My personal favorite:
 - Explaining to stakeholders what reactive power is



Unique construction tasks: Soiling of PV modules





Conclusion



PV industry has many challenges, but they all can be overcome.



Fini Finito Fertig Ferdig Complevit

The End

Пεπερασμένος Законченный ಮುಗಿಸಿದರು Iphele 完成

Questions?



